



water resources / environmental consultants

3 Innwood Circle, Suite 220 • Little Rock, AR 72211 • (501) 225-7779 • Fax (501) 225-6738

October 14, 2016

Mr. Joe Hossley  
Environmental Manager  
Plum Point Energy Station  
2732 S. County Road 623  
P.O. Box 567  
Osceola, AR 72370

**RE: Run-on / Run-off Control Plan  
EPA Final CCR Rule (§ 257.81)  
Plum Point Energy Station Class 3N CCR Landfill  
Osceola, Arkansas**

Dear Mr. Hossley:

FTN Associates, Ltd. has been retained by NRG Energy, Inc. to prepare the following assessment of the EPA's requirements under the HAZARDOUS AND SOLID WASTE MANAGEMENT SYSTEM; DISPOSAL OF COAL COMBUSTION RESIDUALS FROM ELECTRIC UTILITIES (EPA Final CCR Rule) associated with the Stormwater Run-on and Run-off Controls for the CCR Landfill at the Plum Point Energy Station (PPES) near Osceola, Arkansas. Presented below is the project background, summary of findings, limitations, and certification.

## **1.0 BACKGROUND**

As required by §257.81 of the EPA Final CCR Rule, by October 17, 2016, documentation is required to show that the facility's stormwater run-on and run-off control systems have been designed and constructed to meet the 25-year, 24-hour design storm event.

## **2.0 SUMMARY OF FINDINGS**

Based on the results in Tables 1 below, FTN has determined that the PPES CCR Landfill meets the requirements of the EPA Final CCR Rule §257.81 for prevention of stormwater run-on. In addition to the perimeter clay berms which surround the landfill, the facility includes an outer perimeter stormwater channel which routes stormwater around and away from the landfill, preventing run-on. The following table presents the calculated peak flow rates and stormwater

channel capacity for the outer perimeter channel. To determine peak capacity for the channel, it was assumed that a minimum of 6 to 12 inches of freeboard will be maintained in the channel.

**Table 1: Landfill Stormwater Channel Run-On Assessment**

<b>Channel Reach</b>	<b>Peak Storm Discharge, cfs (a)</b>	<b>Ditch Capacity, cfs (b)</b>	<b>Additional Ditch Capacity, cfs (b-a)</b>
Outer Perimeter Channel	35.4	257.4	222.0

Based on the results in the Tables below, FTN has determined that the PPES CCR landfill meets the requirements of EPA Final CCR Rule §257.81 for management of stormwater run-off flows. To manage stormwater run-off from the covered active portions of the landfill and adjacent areas, the PPES CCR landfill maintains an inner perimeter channel system and associated culverts that drain to the facility Stormwater Pond. Additional stormwater that comes in contact with CCR material is treated as leachate and is collected within the lined landfill cells and pumped to onsite storage. The excess capacity shown is due to the system being designed and constructed to handle future expansion of the facility.

**Table 2: Landfill Stormwater Channel Run-Off Assessment**

<b>Channel Reach</b>	<b>Peak Storm Discharge, cfs (a)</b>	<b>Ditch Capacity, cfs (b)</b>	<b>Additional Ditch Capacity, cfs (b-a)</b>
Inner Perimeter Channel	16.8	174.3	157.5

**Table 3: Landfill Stormwater Culvert Run-Off Assessment**

<b>Culvert</b>	<b>Peak Storm Discharge, cfs (a)</b>	<b>Culvert Capacity, cfs (b)</b>	<b>Additional Culvert Capacity, cfs (b-a)</b>
1	16.8	144.4	127.6
2	16.8	174.4	157.6

The resulting stormwater from run-off at the landfill flows to the facility Stormwater Pond. As with the stormwater channels and culverts, the Stormwater Pond was designed and constructed to



Mr. Joe Hossley  
Plum Point Energy Station  
October 14, 2016  
Page 3

handle future conditions. Analysis shows that, at present, approximately 15% of the available storage is utilized in the 25-year, 24-hour storm event. The Stormwater Pond is operated under an NDPEs general stormwater permit (Permit No. ARG160042).

### 3.0 LIMITATIONS


As an authorized representative of FTN, my signature on this document represents that to the best of my knowledge, information and belief in the exercise of my professional judgment, it is my professional opinion that the aforementioned information is accurate as of the date of such signature. Any recommendation, opinion, or decisions by me are made on the basis of my experience, qualifications and professional judgment and are not to be construed as warranties or guaranties. In addition, opinions relating to environmental, geologic, and geotechnical conditions or other estimates are based on available data and actual conditions may vary from those encountered at the times and locations where data are obtained, despite the use of due care.

### 4.0 CERTIFICATION

I, Jason J Ghidotti, PE, being an Arkansas Registered Professional Engineer, do hereby certify to the best of my knowledge, information and belief, that the information contained in this report is true and correct and has been prepared in accordance with the accepted practice of engineering.

We appreciate the opportunity to work with you on this project. If you have questions or comments regarding this project, please do not hesitate to call me or Paul Crawford, PE, PG at (501) 225-7779.

Respectfully submitted,  
FTN ASSOCIATES, LTD.



Jason J Ghidotti, PE

JJG/

R:\PROJECTS\14590-0998-001\TECH\CCR RORO PLAN\RUN-ON RUN-OFF CERTIFICATION LETTER 2016-10-14.DOCX

*Pwz*





water resources / environmental consultants

---

**STORMWATER RUN-ON  
AND  
RUN-OFF CONTROL PLAN**

**PLUM POINT ENERGY STATION  
CLASS 3N LANDFILL**

**PERMIT NO. 0303-S3N  
AFIN: 47-00461**

**OCTOBER 14, 2016**

---

PLUM POINT ENERGY STATION  
CLASS 3N LANDFILL  
STORMWATER RUN-ON AND RUN-OFF CONTROL PLAN

PERMIT NO. 0303-S3N  
AFIN: 47-00461

Prepared for

Plum Point Services Company, LLC  
2732 County Road 623  
Osceola, AR 72370

Prepared by

FTN Associates, Ltd.  
3 Innwood Circle, Suite 220  
Little Rock, AR 72211

FTN No. R14590-0998-001

October 14, 2016

## PROFESSIONAL ENGINEER'S CERTIFICATION

In accordance with §257.81 I certify under penalty of law that I have personally examined and am familiar with the information submitted in this demonstration and all attached documents, and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the submitted information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.

This Stormwater Run-on and Run-off Control Plan for the Plum Point Energy Station Class 3N CCR Landfill near Osceola, Arkansas, was prepared und the direction and supervision of a qualified, State of Arkansas-registered Professional Engineer. Mr. Jason Ghidotti, PE, of FTN Associates, Ltd., was responsible for the overall preparation of the plan.



\_\_\_\_\_  
Jason Ghidotti, PE #10031

\_\_\_\_\_  
Date



---

---

## TABLE OF CONTENTS

PROFESSIONAL ENGINEER’S CERTIFICATION .....	i
PLAN AMENDMENTS .....	ii
1.0 INTRODUCTION .....	1-4
1.1 Purpose of Plan .....	1-4
1.2 Plum Point Energy Station Information.....	1-4
1.3 Permit History .....	1-6
1.4 Existing Conditions of Landfill .....	1-7
2.0 EXISTING STORMWATER CONTROL SYSTEM .....	2-1
3.0 METHODOLOGY .....	3-3
3.1 Prevention of Stormwater Run-on .....	3-4
3.2 Stormwater Run-off .....	3-5
4.0 RESULTS 4-1	
4.1 Prevention of Stormwater Run-on .....	4-1
4.2 Stormwater Run-off .....	4-2

## LIST OF APPENDICES

APPENDIX A:	Definitions
APPENDIX B:	Figures
APPENDIX B:	Run-on Hydrologic and Hydraulic Calculations
APPENDIX C:	Run-off Hydrologic and Hydraulic Calculations

## LIST OF TABLES

Table 4.1	Run-on hydrologic analysis results.....	4-1
Table 4.2	Run-on channel hydraulic analysis results.....	4-1
Table 4.3	Run-off hydrologic analysis results .....	4-2
Table 4.4	Run-off channel hydraulic analysis results .....	4-3
Table 4.5	Run-off culvert hydraulic analysis results .....	4-3
Table 4.6	Run-off pond hydraulic analysis results .....	4-3

---

---

## 1.0 INTRODUCTION

### 1.1 Purpose of Plan

In accordance with 40 CFR §257, *Subpart D - Disposal of Coal Combustion Residuals From Electric Utilities* (the CCR Rule), the purpose of this plan is to provide information that demonstrates that the stormwater run-on and run-off control system for the Plum Point Energy Station (PPES) Class 3N CCR Landfill (the Landfill) will collect and convey a 24-hour, 25-year storm event. From §257.81(a):

*The owner or operator of an existing or new CCR landfill or any lateral expansion of a CCR landfill must design, construct, operate, and maintain:*

*(1) A run-on control system to prevent flow onto the active portion of the CCR unit during the peak discharge from a 24-hour, 25-year storm; and*

*(2) A run-off control system from the active portion of the CCR unit to collect and control at least the water volume resulting from a 24-hour, 25-year storm.*

This Stormwater Run-on and Run-off Control Plan (the Plan) includes:

1. A discussion of how the stormwater run-on and run-off control system has been designed and constructed (Section 2.0 Existing Conditions); and
2. Demonstration of how these controls prevent stormwater run-on and manage run-off at the Landfill (3.0 Methodology).

Appendix A includes definitions for terms included in this Plan.

### 1.2 Plum Point Energy Station Information

The Plum Point Services Company, LLC (PPSC) Plum Point Energy Station (the Plant, PPES) Class 3N Landfill (the Landfill) is located in Mississippi County, approximately 2 miles southeast of Osceola, Arkansas. The 245-acre solid waste management facility is located within the Plant boundaries. The location of the facility is shown on Figure 1 (all figures are located in

Appendix B). The site is characterized by flat terrain and is situated within the Mississippi River floodplain. The Plant is located in an agricultural and industrial area.

PPSC is the owner of the landfill facility but uses a contractor to operate the Landfill for disposal of CCR materials generated at the Plant and general maintenance of the landfill facility.

The Plant generates electricity through the combustion of coal, which produces CCR materials that are captured through the facility air emission control systems and placed in the onsite landfill. The CCRs consist of bottom ash, economizer ash, fly ash, and coal pulverizer rejects.

The bottom ash is the coarsest fraction of the coal ash and is collected in a water-filled trough beneath the steam generation furnace. Bottom ash is composed of angular, glassy particles with a porous surface texture and has the consistency of coarse sand. Coal pulverizer rejects are periodically sluiced to the collection trough beneath the boiler furnaces along with the bottom ash. The economizer ash is the heavier fraction of fly ash and is collected in hoppers and is periodically transferred via dry flight conveyors to a submerged flight conveyor that carries the bottom ash, economizer ash, and coal pulverizer rejects to a concrete basin called the “Bottom Ash Stockout Area.” The collected materials are periodically loaded into haul trucks and taken to the Landfill.

The largest fraction of the CCR material generated from the coal combustion process is fly ash. The fly ash is composed of very fine particles similar to glass and has the consistency of a powder. The plant has a fly ash collection system that captures dry air heater ash and dry scrubber ash in a series of fabric filter and air heater hoppers. The collected material is conveyed to a large silo, which is periodically unloaded into haul trucks and transferred to the Landfill.

The Plant air emission controls include a dry Flue Gas Desulfurization (FGD) system and an activated carbon injection system. The FGD system is designed to cool down the flue gas and remove sulfur dioxide and particulate matter from the gases emitted from the coal-fired boiler. This is accomplished by a chemical reaction using a slurry of calcium hydroxide with the flue gases, while simultaneously allowing the hot flue gases to dry the reaction products (calcium sulfite, calcium sulfate, calcium chloride, and calcium fluoride). The dry reaction products are collected with the fly ash materials in a fabric filter hopper system. The activated carbon

injection system removes mercury from the gases emitted from the coal-fired boiler. The mercury combines chemically with powdered activated carbon and is removed in the same filter system as the fly ash and dry scrubber ash.

The used FGD lime slurry is collected and reused within the FGD system. The retained solids are containerized and periodically transported to the Ash Containment Area, and then to the onsite landfill.

Water is pumped from the Mississippi River and clarified to become either cooling tower makeup water or service water for plant use. The sludge generated from this process is conveyed to a filter press where the solids are containerized and periodically transported to the onsite landfill. The filtrate from this process is pumped back to the clarifiers for treatment.

Although it varies greatly, the Plant generates approximately 500,000 tons of fly ash, bottom ash, and filter cake per year, of which approximately 85% is fly ash, 10% is bottom ash, and 5% is filter cake. The amount placed in the Landfill also varies from year to year, but the average for the past 5 years is approximately 150,000 cubic yards (cy), in-place volume.

The permitted landfill area is located west of the plant site as shown on Figure 2. The landfill is permitted to have 12 disposal areas, varying in size from 15 to 9 acres.

### **1.3 Permit History**

In July 2001, Genesis Environmental Consulting, Inc. (GEC) submitted an application on behalf of Plum Point Energy Associates, LLC, to the Arkansas Department of Environmental Quality (ADEQ) for a solid waste disposal facility at the PPES. In October 2002, ADEQ issued a solid waste permit (0303-S3N) to construct and operate the proposed Class 3N facility.

Prior to construction of the landfill, GEC submitted a minor permit modification application in November 2005 to revise the final landfill grading plan, stormwater control plan, bottom grading plan, earthwork balance calculations, and Construction Quality Assurance (CQA) Plan. The application also included the request for an alternative bottom liner design. ADEQ requested the inclusion of a leachate collection system and Terracon Consultants, Inc. (which had purchased GEC) submitted revised permit documents in July 2006. ADEQ approved the minor permit modification in September 2006. Cell 1 of the landfill and the western

stormwater pond were constructed in 2008. The Plant and the Landfill began operation in March 2010.

Since beginning operation, the landfill constructed an adjacent cell, Cell 3, in 2014 and began placing waste in the new cell in 2015.

#### **1.4 Existing Conditions of Landfill**

The current ADEQ-permitted PPES Class 3N Landfill is approximately 173 acres in size and has been designed to have 12 waste disposal cells (Figure 2, Appendix A). Cells 1 through 10 are about 15 acres in size with approximate dimensions of 1,000 ft by 660 ft. Cells 11 and 12 are narrower and smaller than the remaining cells to accommodate a potential archeological concern located east of the Landfill. Cell 11 is about 9.6 acres (450 ft by 1,000 ft) and Cell 12 is about 10.8 acres (500 ft by 1,000 ft). The permitted disposal capacity (air space) is 22,400,000 cubic yards.

The Landfill has been designed to meet Arkansas Pollution Control and Ecology Commission Regulation No. 22 standards. The bottom of the Landfill is divided to slope north or south to leachate collection sumps. The elevation of the bottom varies from 245 ft National Geodetic Vertical Datum (NGVD) in the center of the Landfill to 230 ft NGVD at the collection sump. The final surface of the Landfill has 4:1 (horizontal to vertical) slopes up to elevation 335 ft NGVD and then slopes at 5% to elevation 365 ft NGVD (Figure 3).

The bottom liner system for Waste Cells 1 and 3 were prepared in accordance with the 2002 permit for the facility (i.e., 12-inch minimum thickness compacted clay liner with a maximum hydraulic conductivity of  $1 \times 10^{-7}$  cm/sec, a 60-mil HDPE liner and a leachate collection system). Waste Cells 1 and 3 comprise the active disposal area of the CCR landfill that received CCR materials after October 19, 2015.

No final cover system has been installed on Waste Cells 1 and 3. However, as shown on Figure 1, the west, north, and south slopes of Cell 1 have received interim soil cover.

---

---

## 2.0 EXISTING STORMWATER CONTROL SYSTEM

The existing stormwater control system for the facility has been developed to collect and convey stormwater around and away from the site to prevent run-on. The Landfill's perimeter ditches generally drain to the west and then south. The outer perimeter ditch directs offsite stormwater around the landfill. The internal perimeter ditch directs onsite stormwater to the facility Stormwater Pond, located on the west side of the landfill. The water from the Stormwater Pond is eventually released through the facility's National Pollutant Discharge Elimination System (NPDES) permitted stormwater outfall to the outer perimeter ditch. An overview of the existing stormwater system is shown on Figure 3 in Appendix B.

The stormwater system is composed of grass-lined channels and culverts at roadway and railroad crossings. Typical details are included in Appendix B, Figure 4. These system components were designed and constructed to convey stormwater and to minimize erosion. Clay-lined perimeter berms and compacted clay expansion berms (Appendix B) at the external edges of each landfill cell also prevent stormwater from entering the cells and becoming run-on.

The south half of Cell 3 is uphill from and is temporarily separated from the north half by a removable clay berm and HDPE liner. As no waste has yet been placed in the south half, stormwater that falls in this area can be collected and discharged as stormwater. When ponding occurs, the water is pumped to a drainage channel that flows south from the landfill. This reduces the amount of potential run-on to the waste mass. In the event stormwater exceeds the amount of available storage behind the temporary berm, it will flow to the Cell 3 sump and be treated as leachate.

As defined by the CCR Rule, stormwater run-off includes any stormwater that falls upon and is discharged from active areas of the landfill. In the case of covered slopes, the stormwater does not come in contact with CCR and can be directly discharged to adjacent stormwater channels. In the case of open landfill areas, the stormwater is either stored within the waste mass or is collected as leachate and discharged as allowed by the facility landfill permit.

For Cells 1 and 3, the leachate flows to lined collection sumps in the northern end of each cell and is pumped to onsite dual-contained holding tanks. Once completed, the leachate will be

routed to a lined storage pond, under construction. The leachate is then either spray applied to the waste to control dust or is transferred to the PPES process system for reuse to reduce usage of clean water. The clay-lined perimeter berms and compacted clay expansion berms shown in Figure 5 also prevent run-off from Cells 1 and 3.

---

### 3.0 METHODOLOGY

Hydrologic and Hydraulic analyses were completed for the run-on and run-off stormwater system based on the 24-hour, 25-year storm event. For the Hydrologic analysis, flows were calculated using the Rational Method, which is given by the following formula:

$$Q = CIA$$

where,

- Q = Flow in cubic feet per second (cfs)
- C = Run-off coefficient (dimensionless)
- I = Rainfall intensity in inches per hour (in/hr)
- A = Drainage area in acres (ac)

The values for the run-off coefficient, C, were based on the slope and the surface conditions. The drainage area, A, was delineated for each basin. Data from the NOAA Atlas 14, Volume 9, Version 2 was used to develop a formula for calculating the rainfall intensity, I. This formula was created by plotting the site's precipitation frequency estimates for the 25-year storm event against the prescribed 24-hour duration. Microsoft Excel was utilized to add a power trend line to the plotted data. The resulting equation of the trend line was used to calculate the intensity and is given by the following equation:

$$I = 20.667 \times T_c^{-0.505}$$

Where,

- I = Rainfall intensity in inches per hour (in/hr)
- T<sub>c</sub> = Time of Concentration (minutes)

The Time of Concentration, T<sub>c</sub>, is time for the most hydraulically distant particle of water to travel to the discharge point of each respective drainage area and is calculated using the methodology described in the USDA Technical Release 55 (TR-55), *Urban Hydrology for Small Watersheds*. The TR-55 method computes T<sub>c</sub> assuming that water moves through a drainage area as either sheet flow, shallow concentrated flow, open channel flow, or some combination thereof. The input variables used in the T<sub>c</sub> calculations include flow length, slope, 2-year 24-hour rainfall

---

depth, and surface roughness of the flow path. The flow length and slope were measured in AutoCAD. The 2-year 24-hour rainfall was taken from the NOAA Atlas 14, Volume 9, Version 2. The open channel dimensions used in the  $T_c$  calculations were based on the landfill construction drawings and recent survey data. The Manning's "n" values used to represent roughness in the  $T_c$  calculations were based on observations from site reconnaissance and best engineering judgment.

For the hydraulic analysis, Manning's formula, the most widely used open channel uniform flow equation, was used to compute the water surface elevation and to evaluate the capacity of the stormwater ditches:

$$V = \frac{1}{n} R^{\frac{2}{3}} S^{\frac{1}{2}}$$

where

- V = Mean velocity (ft/sec)
- n = Manning's coefficient
- R = Hydraulic radius (ft)
- S = Friction slope (ft/ft)

Culvert capacities were evaluated based upon the methodologies set forth in *Hydraulic Design Series No. 5, Hydraulic Design of Highway Culverts (1985)* as prepared by the U.S. Federal Highway Administration. The culverts were analyzed using both inlet and outlet control assumptions to determine which would generate the greater headwater depth.

The internal perimeter channel, culverts and Stormwater Pond were modeled as a combined system using Bentley Systems (Haestad) *PondPack v8i* which uses the methodologies listed above.

The capacity of the external perimeter channel was computed using Bentley *FlowMaster v8i* software using the same methodologies.

### **3.1 Prevention of Stormwater Run-on**

Stormwater is generated from a watershed adjacent to the landfill on the north side. Designated as Basin 1, it is a tilled row-crop area north of the landfill, consists of approximately 32 acres. As it is difficult to ascertain what portion of the area drains south toward the landfill,

the entire area was considered for this analysis. The resulting basin delineation and corresponding longest flow path is shown on Figure 3.

As shown on Figure 3, the areas to the east and south of the site drain away from the landfill, and therefore were not considered for hydrologic and hydraulic analyses of potential stormwater run-on.

The perimeter stormwater channel used to route stormwater around the active landfill to prevent run-on is a large trapezoidal channel of as much as 25 feet in width at the bottom. It is formed by the landfill, Leachate pond and Stormwater Pond perimeter berms and the adjacent elevated railway west of the site. For this analysis, the bottom was assumed to be no more than 15 feet in width.

### **3.2 Control of Stormwater Run-off**

As described in Section 1.0, stormwater run-off is generated from the active portions of the landfill, those that have not received final cover. The active portion of the landfill was divided into two drainage basins for the stormwater run-off hydrologic and hydraulic analysis. As shown on Figure 3, Basin 2 comprises the southern, western and northern slopes of Cell 1 that have received interim soil cover and other areas adjacent to the Cells 1 and 3 that drain to the Stormwater Pond. Basin 2 is 11.1 acres in size. Flow from Basin 2 is not considered leachate as it has not come in contact with waste material.

Basin 3 comprises the open, uncovered portions of Cells 1 and 3, covering 15.1 acres. Stormwater that does not infiltrate the CCR waste material is routed to chimney drains that have been installed in various locations within the waste mass. The surface of the waste is sloped toward the chimney drains, which allow runoff to reach the leachate drainage systems beneath the waste and thence the leachate sumps located in each cell. The leachate is pumped from the sumps via dual-contained pipelines to dual-contained storage tanks, as described in Section 2.0.

Both basins and their corresponding longest flow paths are shown on Figure 3.

## 4.0 RESULTS

Hydrologic and hydraulic calculation for the run-on and run-off analysis are presented in Appendices C and D, respectively.

### 4.1 Stormwater Run-on Results

As described above, one drainage basin, Basin 1, currently contributes to the potential stormwater run-on at the landfill. Hydrologic analysis results for Basin 1 for the 24-hour, 25-year storm event are presented in Appendix C. Results are summarized in Table 4.1, below.

Table 4.1, Run-on hydrologic analysis results.

Basin	Area, A (acres)	Time of Concentration, Tc (minutes)	Composite Run-off Coefficient, C	Rainfall Intensity, I <sub>25</sub> (in/hr)	Peak Discharge, Q <sub>25</sub> (ft <sup>3</sup> /sec)
1	<32	31.0	0.28	4.0	35.4

To prevent run-on, stormwater is conveyed around the landfill via the outer perimeter stormwater channel as shown on Figure 3. Hydraulic analysis of the channel using the calculated peak flow rate from Table 4.1 are presented in Appendix C. Results are summarized in Table 4.2, below.

Table 4.2, Run-on channel hydraulic analysis results.

Channel	Length, L (ft)	Slope, S (ft/ft)	Chanel Depth, D (ft)	Channel Roughness Coefficient, n	Peak Flow, Q <sub>25</sub> (ft <sup>3</sup> /sec)	Peak Velocity, V <sub>25</sub> (ft/sec)	Flow Depth, D <sub>25</sub> (ft)
Outer Perimeter Ditch	3,900	0.003	5.0	0.045	35.4	1.8	1.2

The calculations confirm that the existing outer perimeter stormwater channel will convey the peak flow rates from the 24-hour, 25-year storm event and will prevent stormwater from becoming run-on, running into or inundating the active landfill area.

#### 4.2 Stormwater Run-off Results

As described in Section 3.2, the active portion of the landfill can be divided into two hydrologic basins. Basin 2 is treated as stormwater and flows via the inner perimeter ditch to the Stormwater Pond. Basin 3 is treated as leachate, is collected in the leachate sumps and is pumped to storage. Results from the hydrologic analysis of these two basins for the 24-hour 25-year storm event are presented in Appendix D. Results are summarized in Table 4.3, below.

Table 4.3, Run-off hydrologic analysis results.

<b>Basin</b>	<b>Area, A (acres)</b>	<b>Time of Concentration, Tc (minutes)</b>	<b>Composite Run-off Coefficient, C</b>	<b>Rainfall Intensity, I<sub>25</sub> (in/hr)</b>	<b>Peak Discharge, Q<sub>25</sub> (ft<sup>3</sup>/sec)</b>
2 (Stormwater)	11.1	16.7	0.28	5.40	16.8
3 (Leachate)	15.1	8.1	0.40	7.62	46.1

To manage the runoff from Basin 2, the stormwater is conveyed around the landfill via the inner perimeter stormwater channel and associated culverts to the Stormwater Pond as shown on Figure 3. Hydraulic analysis of this system should consider not only the flow capacity of the inner perimeter channel and culverts, but also the storage capacity of the channel system and the Stormwater Pond using the Basin 2 hydrograph resulting from the 24-hour, 25-year storm. Results of these analyses are presented in Appendix C. Results are summarized in Tables 4.4 through 4.6, below.

Table 4.4, Run-off channel hydraulic analysis results.

Channel	Length, L (ft)	Slope, S (ft/ft)	Chanel Depth, D (ft)	Channel Roughness Coefficient, n	Peak Flow, Q <sub>25</sub> (ft <sup>3</sup> /sec)	Peak Velocity, V <sub>25</sub> (ft/sec)	Flow Depth, D <sub>25</sub> (ft)
Inner Perimeter Ditch	1,200	0.005	4.0	0.045	16.8	2.0	1.0

Table 4.5, Run-off culvert hydraulic analysis results.

Culvert	Length, L (ft)	Slope, S (ft/ft)	Number/ Diameter (in)	Type	Peak Flow, Q <sub>25</sub> (ft <sup>3</sup> /sec)	Headwater Depth, H (ft)
1	100	0.005	2@42"	HDPE/ARCH	16.8	1.1
2	230	0.013	2@42"	HDPE/ARCH	16.8	0.9

Table 4.6, Run-off pond hydraulic analysis results.

Pond	Top Elevation (ft)	Available Storage (ft <sup>3</sup> )	Calculated Peak Elevation (ft)	Calculated Peak Storage (ft <sup>3</sup> )
Inner Perimeter Ditch Ponding	243	84,500	239.8	32,687
Stormwater Pond	243	813,200	235.8	123,143

For stormwater run-off from the active portions of the landfill, the analysis shows that the channel, culverts and Stormwater Pond are of sufficient size to contain the run-off from the 24-hour 25-year storm. The system has excess capacity as it was designed and constructed to handle future conditions as the landfill develops.

For leachate generated by the open portions of the active landfill, the leachate collection and transmission systems have been designed to store and convey the leachate resulting from the 24-hour 25-year storm.

# **APPENDIX A**

---

## **Definitions**

## DEFINITIONS

The following definitions are from §257.53 of the CCR Rule and used in this Plan:

***Active Life (or In Operation):*** the period of operation beginning with the initial placement of CCR in the CCR unit and ending at completion of closure activities in accordance with §257.102.

***Active portion:*** that part of the CCR unit that has received or is receiving CCR or non-CCR waste and that has not completed closure in accordance with §257.102.

***Coal Combustion Residues (CCR):*** fly ash, bottom ash, boiler slag, and flue gas desulfurization materials generated from burning coal for the purpose of generating electricity by electric utilities and independent power producers.

***CCR Landfill:*** an area of land or land excavation that CCR and which is not a surface impoundment, an underground injection well, a salt dome formation, a salt bed formation, an underground or surface coal mine, or a cave. It also includes sand and gravel pits and quarries that receive CCR, CCR piles, and any practice that does not meet the definition of a beneficial use of CCR.

***CCR Unit:*** any CCR landfill, CCR surface impoundment, or lateral expansion of a CCR unit, or a combination of more than one of these units. This term includes both new and existing units.

***Closed Unit or Landfill:*** placement of CCR in a CCR unit has ceased, and the owner or operator has completed closure of the CCR unit in accordance with § 257.102 and has initiated post-closure care in accordance with § 257.104

***Existing CCR Landfill:*** a CCR Landfill that receives CCR both before and after October 15, 2015, or for which construction commenced prior to October 14, 2015. A CCR landfill has commenced construction if the owner or operator has obtained the federal, state, and local approvals or permits necessary to begin physical construction and a continuous onsite physical construction program had begun prior to October 14, 2015.

***Hydraulic Conductivity:*** the rate at which water can move through a permeable medium (i.e., the coefficient of permeability).

***Lateral Expansion:*** a horizontal expansion of the waste boundaries of an existing CCR landfill or existing CCR surface impoundment made after October 14, 2015.

***New CCR Landfill:*** a CCR landfill or lateral expansion of a CCR landfill that first receives CCR or commences construction after October 14, 2015. A CCR landfill has commenced construction if the owner or operator has obtained the federal, state, and local approvals or permits necessary to begin physical construction and a continuous onsite physical construction program had begun after to October 14, 2015.

***Operator:*** the person(s) responsible for the overall operation of a CCR unit.

***Qualified Professional Engineer:*** an individual who is licensed by a state as a Professional Engineer to practice one or more disciplines of engineering and who is qualified by education, technical knowledge and experience to make the specific technical certifications required under this subpart. Professional engineers making these certifications must be currently licensed in the state where the CCR unit(s) is located.

***Recognized and Generally Accepted Good Engineering Practices:*** engineering maintenance or operation activities based on established codes, widely accepted standards, published technical reports, or a practice widely recommended throughout the industry. Such practices generally detail approved ways to perform specific engineering, inspection, or mechanical integrity activities.

***Run-Off:*** any rainwater, leachate, or other liquid that drains over land from any part of a CCR landfill or lateral expansion of a CCR landfill.

***Run-On:*** any rainwater, leachate, or other liquid that drains over land onto any part of a CCR landfill or lateral expansion of a CCR landfill.

***Structural Components:*** liners, leachate collection and removal systems, final covers, run-on and run-off systems, inflow design flood control systems, and any other component used in the construction and operation of the CCR unit that is necessary to ensure the integrity of the unit and that the contents of the unit are not released into the environment.

# **APPENDIX B**

---

**Figures**




Figure 1 Site location map.

**PLUM POINT SERVICES COMPANY, LLC**  
**PLUM POINT ENERGY STATION CLASS 3N LANDFILL**  
**STORMWATER RUN-ON/RUN-OFF PLAN**


OSCEOLA, ARKANSAS

**FIGURE 2**  
**EXISTING CONDITIONS**



DRAWN BY:	FILE NAME:
<i>gde</i>	FG02.DWG
APPROVED:	PROJECT NO.
<i>gde</i>	14590-0998-001
SCALE:	DATE:
1" = 150'	10/13/16
SHEET NO.	
1 OF 1	



- LEGEND**
- WASTE CELL BOUNDARY
  - EXISTING PERMITTED BOUNDARY
  - - - 230 --- EXISTING INDEX CONTOUR (5-FT)
  - - - EXISTING INTERMEDIATE CONTOUR (1-FT)
  - ==== EXISTING GRAVEL ROAD
  - EXISTING FENCE
  - ⊕ EXISTING POWER POLE
  - EXISTING OVERHEAD ELECTRIC LINE



NOTE:  
 TOPOGRAPHIC INFORMATION IS FROM SURVEYS CONDUCTED BY HARMON SURVEYING, INC. ON OCTOBER 2014 (CELL 3), DECEMBER 2015 (CELLS 1 AND 3) AND OCTOBER 2011.



- LEGEND**
- WASTE CELL BOUNDARY
  - EXISTING PERMITTED BOUNDARY
  - - - 230 --- EXISTING INDEX CONTOUR (5-FT)
  - - - EXISTING INTERMEDIATE CONTOUR (1-FT)
  - ==== EXISTING GRAVEL ROAD
  - EXISTING FENCE
  - o EXISTING POWER POLE
  - EXISTING OVERHEAD ELECTRIC LINE
  - DRAINAGE BASIN
  - STORMWATER DITCH
  - CULVERT
  - o OVERLAND FLOW DIRECTION

**NOTE:**  
 TOPOGRAPHIC INFORMATION IS FROM SURVEYS CONDUCTED BY HARMON SURVEYING, INC. ON OCTOBER 2014 (CELL 3), DECEMBER 2015 (CELLS 1 AND 3) AND OCTOBER 2011.

**PLUM POINT SERVICES COMPANY, LLC**  
**PLUM POINT ENERGY STATION CLASS 3N LANDFILL**  
**STORMWATER RUN-ON/RUN-OFF PLAN**  
**OSCEOLA, ARKANSAS**

**FIGURE 3**  
**STORMWATER PLAN**

DRAWN BY: <i>gpe</i>	FILE NAME: FG03.DWG
APPROVED: <i>gpe</i>	PROJECT NO. 14590-0998-001
SCALE: 1" = 100'	DATE: 10/13/16
SHEET NO. 1 OF 1	




Figure 4. Typical Stormwater Details.




Figure 5. Landfill Berm Details.

# **APPENDIX C**

---

## **Run-on Hydrologic and Hydraulic Calculations**

# T<sub>c</sub> and Flow Calculations for Basin 1

## INPUT

Flow Type	Length	Slope
Overland	400	0.005
Shallow	400	0.005
Channel	1300	0.005
Total Length	2100	

## OVERLAND FLOW

(Sheet Flow)

$$T_c = \frac{0.007 \cdot (n \cdot L)^{0.8}}{(P_{2yr, 24hr})^{0.5} \cdot s^{0.4}} \quad (\text{TR-55})$$

Minimum Assumed Slope = 0.0005 ft/ft  
Rainfall = 2yr, 24-hour 3.82 in

Segment	Length, ft	Manning's	Slope (ft/ft)	T <sub>c</sub> (hr)
1	400	0.060	0.0050	0.379

## SHALLOW FLOW

$$\text{Unpaved } V = 16.1345 \cdot S^{0.5} \quad (\text{TR-55})$$

$$t = L/3600V$$

$$\text{Paved } V = 20.3282 \cdot S^{0.5}$$

Segment	Length, ft	Paved	Slope (ft/ft)	Velocity	T <sub>c</sub>
2	400	No	0.005	1.14	0.097

T<sub>c</sub> in hr

## CHANNEL FLOW

$$t = L/3600V$$

$$V = (1.49 \cdot r^{2/3} \cdot s^{0.5}) / n \quad (\text{TR-55})$$

Segment	Length, ft	Slope (ft/ft)	ManningsN	Side Slope	Bottom Width	Depth	Area	WP*	HydrRadius	Velocity	T <sub>c</sub> (hr)
3	1300.00	0.01	0.020	2	15	3	63.000	28.416	2.22	8.96	0.040

hydraulic radius = area/wetted perimeter

\*Note: Assume channel is full

## TOTAL TIME

$$T_c = T_{\text{SHEET}} + T_{\text{SHALLOW}} + T_{\text{CHANNEL}}$$

Segment	T <sub>c</sub> (hr)	T <sub>c</sub> (min)
1	0.379	22.74
2	0.097	5.84
3	0.040	2.42
<b>CUMULATIVE T<sub>c</sub></b>	<b>0.517</b>	<b>31.0</b>

## FLOW CALCULATION

$$Q = CIA$$

C =	0.28
I (in/hr) =	4.02
A (ac) =	31.50
<b>Therefore Q =</b>	<b>35.44</b> cfs

---

## Worksheet for Outer Perimeter Channel

---

### Project Description

Friction Method	Manning Formula
Solve For	Normal Depth

### Input Data

Roughness Coefficient	0.045	
Channel Slope	0.00300	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	2.00	ft/ft (H:V)
Bottom Width	15.00	ft
Discharge	35.44	ft <sup>3</sup> /s

### Results

Normal Depth	1.15	ft
Flow Area	19.81	ft <sup>2</sup>
Wetted Perimeter	20.12	ft
Hydraulic Radius	0.98	ft
Top Width	19.58	ft
Critical Depth	0.54	ft
Critical Slope	0.03768	ft/ft
Velocity	1.79	ft/s
Velocity Head	0.05	ft
Specific Energy	1.20	ft
Froude Number	0.31	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.15	ft
Critical Depth	0.54	ft
Channel Slope	0.00300	ft/ft

---

## Worksheet for Outer Perimeter Channel - Max Capacity

---

### Project Description

Friction Method	Manning Formula
Solve For	Discharge

### Input Data

Roughness Coefficient	0.045	
Channel Slope	0.00300	ft/ft
Normal Depth	3.50	ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	2.00	ft/ft (H:V)
Bottom Width	15.00	ft

### Results

Discharge	257.35	ft <sup>3</sup> /s
Flow Area	77.00	ft <sup>2</sup>
Wetted Perimeter	30.65	ft
Hydraulic Radius	2.51	ft
Top Width	29.00	ft
Critical Depth	1.91	ft
Critical Slope	0.02664	ft/ft
Velocity	3.34	ft/s
Velocity Head	0.17	ft
Specific Energy	3.67	ft
Froude Number	0.36	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	3.50	ft
Critical Depth	1.91	ft
Channel Slope	0.00300	ft/ft

# **APPENDIX D**

---

## **Run-off Hydrologic and Hydraulic Calculations**

# T<sub>c</sub> and Flow Calculations for Basin 2

## INPUT

Flow Type	Length	Slope
Overland	230	0.250
Shallow	40	0.005
Channel	580	0.005
Total Length	850	

## OVERLAND FLOW

(Sheet Flow)

$$T_c = \frac{.007 * (n * L)^{.8}}{(P_{2yr, 24hr})^{.5} * s^{.4}} \quad (\text{TR-55})$$

Minimum Assumed Slope = 0.0005 ft/ft  
Rainfall = 2yr, 24-hour 3.82 in

Segment	Length, ft	Manning's	Slope (ft/ft)	T <sub>c</sub> (hr)
1	230	0.450	0.2500	0.255

## SHALLOW FLOW

$$\text{Unpaved } V = 16.1345 * S^{.5} \quad (\text{TR-55})$$

$$t = L/3600V$$

$$\text{Paved } V = 20.3282 * S^{.5}$$

Segment	Length, ft	Paved	Slope (ft/ft)	Velocity	T <sub>c</sub>
2	40	No	0.020	2.28	0.005

T<sub>c</sub> in hr

## CHANNEL FLOW

$$t = L/3600V$$

$$V = (1.49 * r^{.486} / (3 * s^{.1486})) / n \quad (\text{TR-55})$$

Segment	Length, ft	Slope (ft/ft)	Manning's N	Side Slope	Bottom Width	Depth	Area	WP*	HydrRadius	Velocity	T <sub>c</sub> (hr)
3	580.00	0.01	0.020	2	15	3	63.000	28.416	2.22	8.96	0.018

hydraulic radius = area/wetted perimeter

\*Note: Assume channel is full

## TOTAL TIME

$$T_c = T_{\text{SHEET}} + T_{\text{SHALLOW}} + T_{\text{CHANNEL}}$$

Segment	T <sub>c</sub> (hr)	T <sub>c</sub> (min)
1	0.255	15.31
2	0.005	0.29
3	0.018	1.08
<b>CUMULATIVE T<sub>c</sub></b>	<b>0.278</b>	<b>16.7</b>

## FLOW CALCULATION

$$Q = CIA$$

C =	0.28
I (in/hr) =	5.40
A (ac) =	11.10
<b>Therefore Q =</b>	<b>16.78</b> cfs

# T<sub>c</sub> and Flow Calculations for Basin 3

## INPUT

Flow Type	Length	Slope
Overland	250	0.330
Shallow	660	0.015
Channel	0	0.005
Total Length	910	

## OVERLAND FLOW

(Sheet Flow)

$$T_c = \frac{.007 * (n * L)^{.8}}{(P_{2yr, 24hr})^{.5} * s^{.4}} \quad (\text{TR-55})$$

Minimum Assumed Slope = 0.0005 ft/ft  
Rainfall = 2yr, 24-hour 3.82 in

Segment	Length, ft	Manning's	Slope (ft/ft)	T <sub>c</sub> (hr)
1	250	0.050	0.3300	0.042

## SHALLOW FLOW

$$\text{Unpaved } V = 16.1345 * S^{.5} \quad (\text{TR-55})$$

$$t = L/3600V$$

$$\text{Paved } V = 20.3282 * S^{.5}$$

Segment	Length, ft	Paved	Slope (ft/ft)	Velocity	T <sub>c</sub>
2	660	No	0.015	1.98	0.093

T<sub>c</sub> in hr

## CHANNEL FLOW

$$t = L/3600V$$

$$V = (1.49 * r^{.486} / (3 * s^{.148} * n)) \quad (\text{TR-55})$$

Segment	Length, ft	Slope (ft/ft)	Manning's N	Side Slope	Bottom Width	Depth	Area	WP*	HydrRadius	Velocity	T <sub>c</sub> (hr)
3	0.00	0.01	0.020	2	15	3	63.000	28.416	2.22	8.96	0.000

hydraulic radius = area/wetted perimeter

\*Note: Assume channel is full

## TOTAL TIME

$$T_c = T_{\text{SHEET}} + T_{\text{SHALLOW}} + T_{\text{CHANNEL}}$$

Segment	T <sub>c</sub> (hr)	T <sub>c</sub> (min)
1	0.042	2.53
2	0.093	5.57
3	0.000	0.00
<b>CUMULATIVE T<sub>c</sub></b>	<b>0.135</b>	<b>8.1</b>

## FLOW CALCULATION

$$Q = CIA$$

C =	0.40
I (in/hr) =	7.62
A (ac) =	15.10
<b>Therefore Q =</b>	<b>46.05</b> cfs

---

## Worksheet for Inner Perimeter Channel

---

### Project Description

Friction Method	Manning Formula
Solve For	Normal Depth

### Input Data

Roughness Coefficient	0.045	
Channel Slope	0.00500	ft/ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	2.00	ft/ft (H:V)
Bottom Width	6.00	ft
Discharge	16.80	ft <sup>3</sup> /s

### Results

Normal Depth	1.04	ft
Flow Area	8.42	ft <sup>2</sup>
Wetted Perimeter	10.66	ft
Hydraulic Radius	0.79	ft
Top Width	10.17	ft
Critical Depth	0.58	ft
Critical Slope	0.03878	ft/ft
Velocity	2.00	ft/s
Velocity Head	0.06	ft
Specific Energy	1.10	ft
Froude Number	0.39	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	1.04	ft
Critical Depth	0.58	ft
Channel Slope	0.00500	ft/ft

## Worksheet for Inner Perimeter Channel - Max Capacity

### Project Description

Friction Method	Manning Formula
Solve For	Discharge

### Input Data

Roughness Coefficient	0.045	
Channel Slope	0.00500	ft/ft
Normal Depth	3.50	ft
Left Side Slope	2.00	ft/ft (H:V)
Right Side Slope	2.00	ft/ft (H:V)
Bottom Width	6.00	ft

### Results

Discharge	174.29	ft <sup>3</sup> /s
Flow Area	45.50	ft <sup>2</sup>
Wetted Perimeter	21.65	ft
Hydraulic Radius	2.10	ft
Top Width	20.00	ft
Critical Depth	2.29	ft
Critical Slope	0.02766	ft/ft
Velocity	3.83	ft/s
Velocity Head	0.23	ft
Specific Energy	3.73	ft
Froude Number	0.45	
Flow Type	Subcritical	

### GVF Input Data

Downstream Depth	0.00	ft
Length	0.00	ft
Number Of Steps	0	

### GVF Output Data

Upstream Depth	0.00	ft
Profile Description		
Profile Headloss	0.00	ft
Downstream Velocity	Infinity	ft/s
Upstream Velocity	Infinity	ft/s
Normal Depth	3.50	ft
Critical Depth	2.29	ft
Channel Slope	0.00500	ft/ft

# Culvert Calculator Report

## Culvert 1

Solve For: Headwater Elevation

Culvert Summary			
Allowable HW Elevation	243.00 ft	Headwater Depth/Height	0.42
Computed Headwater Elev.	240.09 ft	Discharge	16.80 cfs
Inlet Control HW Elev.	240.00 ft	Tailwater Elevation	240.00 ft
Outlet Control HW Elev.	240.09 ft	Control Type	Outlet Control

---

Grades			
Upstream Invert	239.00 ft	Downstream Invert	238.50 ft
Length	100.00 ft	Constructed Slope	0.005000 ft/ft

---

Hydraulic Profile			
Profile	S1	Depth, Downstream	1.50 ft
Slope Type	Steep	Normal Depth	0.58 ft
Flow Regime	Subcritical	Critical Depth	0.64 ft
Velocity Downstream	1.48 ft/s	Critical Slope	0.003499 ft/ft

---

Section			
Section Shape	Arch	Mannings Coefficient	0.013
Section Material	Concrete	Span	4.26 ft
Section Size	51.12 x 31.31 inch	Rise	2.61 ft
Number Sections	2		

---

Outlet Control Properties			
Outlet Control HW Elev.	240.09 ft	Upstream Velocity Head	0.09 ft
Ke	0.20	Entrance Loss	0.02 ft

---

Inlet Control Properties			
Inlet Control HW Elev.	240.00 ft	Flow Control	Unsubmerged
Inlet Type	Groove end projecting (arch)	Area Full	17.3 ft <sup>2</sup>
K	0.00450	HDS 5 Chart	0
M	2.00000	HDS 5 Scale	0
C	0.03170	Equation Form	1
Y	0.69000		

# Culvert Calculator Report

## Culvert 2

Solve For: Headwater Elevation

Culvert Summary			
Allowable HW Elevation	243.00 ft	Headwater Depth/Height	0.36
Computed Headwater Elev:	238.94 ft	Discharge	16.80 cfs
Inlet Control HW Elev.	238.87 ft	Tailwater Elevation	236.00 ft
Outlet Control HW Elev.	238.94 ft	Control Type	Entrance Control

---

Grades			
Upstream Invert	238.00 ft	Downstream Invert	235.00 ft
Length	230.00 ft	Constructed Slope	0.013043 ft/ft

---

Hydraulic Profile			
Profile	CompositeS1S2	Depth, Downstream	1.00 ft
Slope Type	Steep	Normal Depth	0.46 ft
Flow Regime	N/A	Critical Depth	0.64 ft
Velocity Downstream	2.31 ft/s	Critical Slope	0.003499 ft/ft

---

Section			
Section Shape	Arch	Mannings Coefficient	0.013
Section Material	Concrete	Span	4.26 ft
Section Size	51.12 x 31.31 inch	Rise	2.61 ft
Number Sections	2		

---

Outlet Control Properties			
Outlet Control HW Elev.	238.94 ft	Upstream Velocity Head	0.25 ft
Ke	0.20	Entrance Loss	0.05 ft

---

Inlet Control Properties			
Inlet Control HW Elev.	238.87 ft	Flow Control	Unsubmerged
Inlet Type	Groove end projecting (arch)	Area Full	17.3 ft <sup>2</sup>
K	0.00450	HDS 5 Chart	0
M	2.00000	HDS 5 Scale	0
C	0.03170	Equation Form	1
Y	0.69000		

## Scenario Calculation Summary

Scenario Summary	
ID	47
Label	Post-Development 25 Year Storm
Notes	
Active Topology	Post-Development Active Topology
Hydrology	Post-Development Hydrology
Rainfall Runoff	Synthetic 25 Year
Physical	Post-Development Physical
Initial Condition	Post-Development Initial Condition
Boundary Condition	Post-Development Boundary Condition
Infiltration and Inflow	Post-Development Infiltration and Inflow
Output	Post-Development Output
User Data Extensions	Post-Development User Data Extensions
PondPack Engine Calculation Options	Base Calculation Options

Output Summary			
Output Increment	3.0 min	Duration	1,440.0 min

Rainfall Summary			
Return Event Tag	25	Rainfall Type	Time-Depth Curve
Total Depth	6.6 in	Storm Event	25YR24HR-TypeII

ICPM Output Summary			
Target Convergence	0.00 ft <sup>3</sup> /s	ICPM Time Step	3.0 min
Maximum Iterations	35		

### Executive Summary (Nodes)

Label	Scenario	Return Event (years)	Truncation	Hydrograph Volume (ft <sup>3</sup> )	Time to Peak (min)	Peak Flow (ft <sup>3</sup> /s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ft <sup>3</sup> )
Covered Landfill	Post-Development 25 Year Storm	25	None	207,051.000	723.0	68.67	(N/A)	(N/A)
Inner Channel (IN)	Post-Development 25 Year Storm	25	None	207,051.000	723.0	68.67	(N/A)	(N/A)
Inner Channel (OUT)	Post-Development 25 Year Storm	25	None	205,942.000	729.0	51.94	239.82	32,687.000
Outfall	Post-Development 25 Year Storm	25	None	121,498.000	852.0	3.73	(N/A)	(N/A)

## Scenario Calculation Summary

### Executive Summary (Nodes)

Label	Scenario	Return Event (years)	Truncation	Hydrograph Volume (ft <sup>3</sup> )	Time to Peak (min)	Peak Flow (ft <sup>3</sup> /s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ft <sup>3</sup> )
West Pond (IN)	Post-Development 25 Year Storm	25	None	205,942.000	729.0	51.94	(N/A)	(N/A)
West Pond (OUT)	Post-Development 25 Year Storm	25	None	121,498.000	852.0	3.73	235.82	123,143.000


### Executive Summary (Links)

Label	Type	Location	Hydrograph Volume (ft <sup>3</sup> )	Peak Time (min)	Peak Flow (ft <sup>3</sup> /s)	End Point	Node Flow Direction
2x42 RCPA	Pond Outlet	Upstream	207,051.000	723.0	68.67	Inner Channel	Pond Inflow
2x42 RCPA	Pond Outlet	Outflow	205,942.000	729.0	51.94	Inner Channel	Pond Outflow
2x42 RCPA	Pond Outlet	Link	205,942.000	729.0	51.94		
2x42 RCPA	Pond Outlet	Downstream	205,942.000	729.0	51.94	West Pond	
36" RCP	Pond Outlet	Upstream	205,942.000	729.0	51.94	West Pond	Pond Inflow
36" RCP	Pond Outlet	Outflow	121,498.000	852.0	3.73	West Pond	Pond Outflow
36" RCP	Pond Outlet	Link	121,498.000	852.0	3.73		
36" RCP	Pond Outlet	Downstream	121,498.000	852.0	3.73	Outfall	

### Messages

Message Id	-1
Scenario	Post-Development 25 Year Storm
Element Type	Composite Outlet Structure
Element Id	23
Label	Inner Channel Culverts
Time	(N/A)
Message	A user defined rating table is being used with a non-free outfall tailwater setting. For user defined rating tables it is suggested to use only free outfall tailwater as tailwater effects are not handled.
Source	Precalculation

Graph - 2



West Pond - Post-Development 25 Year Storm - Flow (Total In)    West Pond - Post-Development 25 Year Storm - Flow (Total Out)    West Pond - Post-Development 25 Year Storm - Volume    West Pond - Post-Development 25 Year Storm - Elevation  
Inner Channel - Post-Development 25 Year Storm - Flow (Total In)    Inner Channel - Post-Development 25 Year Storm - Flow (Total Out)    Inner Channel - Post-Development 25 Year Storm - Volume    Inner Channel - Post-Development 25 Year Storm - Elevation