

MWVG

Midwest Generation, LLC
Will County Generating Station

Preliminary Written Closure Plan for South Ash Pond 2 & South Ash Pond 3



Revision 1

October 29, 2021

Issue Purpose: Use

Project No.: 12661-124

55 East Monroe Street
Chicago, IL 60603-5780 USA
312-269-2000
www.sargentlundy.com



TABLE OF CONTENTS

Table of Contents i

1.0 Purpose & Scope..... 1

 1.1 Purpose..... 1

 1.2 Scope..... 1

2.0 Closure Plan Narrative Description..... 1

3.0 Final Cover System Description 2

 3.1 Establish Grade & Support for Final Cover System 3

 3.2 Low Permeability Layer 3

 3.3 Final Protective Layer 6

4.0 Estimated Maximum Inventory of CCR 6

5.0 Estimated Cover Surface Area..... 6

6.0 Closure Schedule 7

7.0 Amendments to Closure Plan 8

8.0 Completion of Closure Activities..... 8

9.0 Certification 9

10.0 References 9

1.0 PURPOSE & SCOPE

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)

Federal CCR Rule Reference: 40 CFR 257.102(b)

1.1 PURPOSE

South Ash Pond 2 and South Ash Pond 3 at Midwest Generation, LLC's (MWG) Will County Generating Station ("Will County" or the "Station") are existing coal combustion residual (CCR) surface impoundments that are regulated by the Illinois Pollution Control Board's "Standards for the Disposal of Coal Combustion Residuals in CCR Surface Impoundments." These regulations are codified in Part 845 to Title 35 of the Illinois Administrative Code (35 Ill. Adm. Code 845, Ref. 1) and are also referred to herein as the "Illinois CCR Rule." South Ash Ponds 2 and 3 are also regulated by the U.S. Environmental Protection Agency's "Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments," 40 CFR Part 257 Subpart D (Ref. 2), also referred to herein as the "Federal CCR Rule."

Pursuant to 35 Ill. Adm. Code 845.720(a) and 40 CFR 257.102(b), this document provides the preliminary written closure plan for South Ash Ponds 2 and 3 at Will County. MWG intends to close these CCR surface impoundments by leaving the impounded CCR in place and installing final cover systems over the impoundments in accordance with 35 Ill. Adm. Code 845.750 and 40 CFR 257.102(d). This plan describes the steps necessary to close South Ash Ponds 2 and 3 in this manner.

1.2 SCOPE

Per the 2016 Water Infrastructure Improvements for the Nation (WIIN) Act, South Ash Ponds 2 and 3 will continue to be subject to both the Illinois and Federal CCR Rules until the U.S. EPA approves the Illinois EPA's CCR permit program. The Illinois EPA has yet to publish a timeline for submitting its proposed CCR permit program to the U.S. EPA for approval, and so this preliminary written closure plan has been prepared pursuant to both sets of regulations.

2.0 CLOSURE PLAN NARRATIVE DESCRIPTION

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(1)(A) & 845.750(a)

Federal CCR Rule Reference: 40 CFR 257.102(b)(1)(i) & 257.102(d)(1)

Pursuant to 35 Ill. Adm. Code 845.750(a) and 40 CFR 257.102(d), South Ash Ponds 2 and 3 will be closed by leaving the CCR stored in each pond in place and installing a final cover system over each impoundment. Each final cover system will be designed in accordance with the requirements specified in 35 Ill. Adm. Code 845.750(c) and 40 CFR 257.102(d)(3) and as described in the following sections of this closure plan.

The anticipated closure in-place of South Ash Ponds 2 and 3 will be performed in accordance with the following sequential steps:

1. Ceasing all CCR and non-CCR inflows to each pond;
2. Drawing down the free surface water in each pond by evaporation and by draining water into the concrete overflow trough at the west end of each pond;
3. Once the water elevation is below the weir elevation, promoting additional drainage and dewatering by:
 - a. Excavating sumps and trenches within the ash material,
 - b. Using portable pumps as necessary to remove additional water by pumping water over the weir into each pond's concrete overflow trough, and/or
 - c. Utilizing earthmoving equipment to move the ash within each pond;
4. Upon completion of dewatering and stabilization of the impounded ash, grading the ash material to establish the slopes for the final cover system;
5. Placing and grading general fill material within a pond if enough ash is not available in the pond to establish the slopes for the final cover system;
6. Installing the low permeability layer of the final cover system;
7. Installing the final protective layer over the low permeability layer;
8. Seeding the final protective layer; and
9. Initiating post-closure monitoring of vegetation, groundwater, and final cover system integrity.

3.0 FINAL COVER SYSTEM DESCRIPTION

Illinois CCR Rule References: 35 Ill. Adm. Code 845.720(a)(1)(C) & 845.750(a)

Federal CCR Rule References: 40 CFR 257.102(b)(1)(iii) & 257.102(d)(1)

Pursuant to the closure performance standards prescribed in 35 Ill. Adm. Code 845.750(a) and 40 CFR 257.102(d)(1), the final cover systems encapsulating the CCR in South Ash Ponds 2 and 3 will:

1. Minimize the post-closure infiltration of liquid into the CCR;
2. Minimize the risk of release of CCR or contaminated run-off to the ground or surface waters, or to the atmosphere;
3. Preclude the probability of future impoundment of water, sediment, or slurry;
4. Provide major slope stability to prevent sloughing of the final cover systems during the closure and post-closure care period;
5. Minimize future maintenance; and
6. Allow closure activities to be completed as quickly as practical consistent with recognized and generally accepted good engineering practices;

In addition to the preceding performance criteria, the final cover systems installed over South Ash Ponds 2 and 3 must meet the design criteria promulgated by 35 Ill. Adm. Code 845.750(c) and 40 CFR 257.102(d)(3), both of which require the final cover system to consist of at least two layers: a lower, low-permeability layer for infiltration control and an upper, final protective layer for erosion control and for protecting the low permeability layer. MWG plans to install final cover systems over South Ash Ponds 2 and 3 that consist of a 60-mil HDPE geomembrane under a minimum of three feet of vegetated, earthen material.

3.1 ESTABLISH GRADE & SUPPORT FOR FINAL COVER SYSTEM

Illinois CCR Rule References: 35 Ill. Adm. Code 845.750(a)(2), 845.750(a)(3), & 845.750(c)(3)

Federal CCR Rule References: 40 CFR 257.102(d)(1)(ii), 257.102(d)(1)(iii), & 257.102(d)(3)(i)(D)

To accomplish the performance requirements stipulated by 35 Ill. Adm. Code 845.750 and 40 CFR 257.102(d), the CCR remaining in South Ash Ponds 2 and 3 will be graded to direct non-contact storm water run-off to each pond's concrete overflow trough at its western end. Additional general fill material will be placed in a pond to establish the lines and grades for this storm water management scheme if sufficient quantities of CCR are not present in the pond for this purpose at the time of closure. The slopes of this foundation layer for each pond's final cover system will be steep enough to prevent storm water from ponding over the cap but flat enough to limit erosion caused by the storm water run-off. These slopes will also be designed to accommodate potential settling and subsidence while maintaining a positive drainage strategy. In addition, the foundation layer's slopes (and the final cover system in general) will also include measures that provide slope stability to prevent the sloughing or movement of the final cover system during the closure and post-closure care period. Finally, the foundation layer surface will be prepared such that it is free from large, protruding, or sharp materials that could otherwise cause damage to the overlying low permeability layer.

3.2 LOW PERMEABILITY LAYER

Illinois CCR Rule References: 35 Ill. Adm. Code 845.750(a)(1) & 845.750(c)(1)

Federal CCR Rule References: 40 CFR 257.102(d)(1)(i) & 257.102(d)(3)(ii)(A)

A low permeability layer will be placed on top of the graded CCR (and general fill if necessary) in South Ash Ponds 2 and 3 to minimize the infiltration of liquids through each pond during their post-closure lives. The low permeability layer will control, minimize, and eliminate, to the maximum extent feasible, post-closure infiltration of liquids into the waste and releases of CCR, leachate, or contaminated run-off to the ground or surface waters or to the atmosphere.

Table 1 lists the design criteria for the low permeability layer of a final cover system installed over a CCR surface impoundment as promulgated by the Illinois and Federal CCR Rules. By comparison, the Illinois

CCR Rule's design criteria for the low permeability layer are either as protective or more protective of human health and the environment than the design criteria promulgated by the Federal CCR Rule. Accordingly, the low permeability layers in the final cover systems for South Ash Ponds 2 and 3 will be designed in accordance with the design criteria promulgated by the Illinois CCR Rule.

Table 1 – Comparison of Illinois and Federal CCR Rules' Design Criteria for Low Permeability Layer in a CCR Surface Impoundment's Final Cover System

Construction Material	Parameter	Illinois CCR Rule Design Criterion (35 Ill. Adm. Code 845.750(c)(1))	Federal CCR Rule Design Criterion (40 CFR 257.102(d)(3))
Earthen Material	Thickness	3 feet minimum	1.5 feet minimum
	Hydraulic Conductivity	Least of: <ul style="list-style-type: none"> Permeability of any bottom liner system or natural subsoils 1×10^{-7} cm/sec 	Least of: <ul style="list-style-type: none"> Permeability of any bottom liner system or natural subsoils 1×10^{-5} cm/sec
	Compaction	Minimize void spaces	--
Geomembrane	Thickness	40 mil	--
	Hydraulic Flux	Equivalent or superior reduction in infiltration as a low permeability layer constructed with earthen material	Equivalent or superior reduction in infiltration as a low permeability layer constructed with earthen material
	Prepared Subgrade	Free from sharp objects and other materials that may cause damage	--

South Ash Ponds 2 and 3 both have a 60-mil HDPE geomembrane liner on the floors and sides of the ponds; therefore, the low permeability layer in each pond's final cover system must have a permeability that is equal to or less than the effective permeability of the existing liner. In lieu of using earthen materials to minimize the infiltration of liquids through the closed ponds, MWG plans to install a geomembrane-based low permeability layer over each pond pursuant to 35 Ill. Adm. Code 845.750(c)(1)(B) and 40 CFR 257.102(d)(3)(ii)(A). To provide an equivalent or superior reduction in infiltration as a low permeability layer constructed with earthen material in accordance with 35 Ill. Adm. Code 845.750(c)(1)(A) and 40 CFR 257.102(d)(3)(i)(A)–(B), MWG plans to install a 60-mil HDPE geomembrane for the low permeability layer in each pond's final cover system.

As required by 35 Ill. Adm. Code 845.750(c)(1)(B)(i) and 40 CFR 257.102(d)(3)(ii)(A), Table 2 demonstrates that a 60-mil HDPE geomembrane will provide a superior reduction in infiltration when compared to a 3-foot-thick layer of earthen material with a hydraulic conductivity of 1×10^{-7} cm/sec. The liquid flow rate through a 3-

foot-thick layer of earthen material is calculated using the equation derived from Darcy’s Law for gravity flow through porous media that is specified by the Illinois and Federal CCR Rules as the basis for demonstrating compliance with both rules’ alternative composite liner design criteria (Ref. 1, §845.400(c)(3); Ref. 2, Eq. 1). Meanwhile, the liquid flow rate through a geomembrane liner is calculated using Bernoulli’s equation for free flow through an orifice based on the assumption that one 2-mm-diameter hole is present in the geomembrane for every acre (4,000 m²) of liner (Ref. 3). Both liquid flow rates calculated in Table 2 are based on the assumption that 5.53 inches (0.14 meter) of hydraulic head is present on the low permeability layer, which is the estimated 25-year, 24-hour precipitation depth at the Station (Ref. 4). This is a conservative assumption because the final cover system will be sloped to preclude the build-up of liquid on the low permeability layer.

Table 2 – Liquid Flow Rate Comparison Between Low Permeability Layers Constructed Using Geomembrane & Earthen Material

Parameter	Symbol	Value
Liquid Flow Rate Through Earthen Material		
Hydraulic Conductivity	k	1×10^{-9} m/sec
Hydraulic Head Above Layer	h	0.14 m
Layer Thickness	t	3 ft = 0.91 m
Hydraulic Gradient Through Earthen Material	$i = h / t$	0.15
Liquid Flow Rate Through Layer per Acre of Final Cover System (Ref. 1, §845.400(c)(3); Ref. 2, Eq. 1).	$q = k \times (i + 1)$	1.15×10^{-9} m ³ /sec/m ²
Liquid Flow Rate Through Geomembrane		
Hole Area in Geomembrane	a	3.1 mm ² / 4000 m ²
Acceleration Due to Gravity	g	9.81 m/sec ²
Hydraulic Head Above Layer	h	0.14 m
Liquid Flow Rate Through Layer per Unit Area (Ref. 3)	$q = 0.6a(2gh)^{0.5}$	7.71×10^{-10} m ³ /sec/m ²

3.3 FINAL PROTECTIVE LAYER

Illinois CCR Rule References: 35 Ill. Adm. Code 845.750(c)(2)

Federal CCR Rule Reference: 40 CFR 257.102(d)(3)(ii)(B)

A final protective layer consisting of a minimum of three feet of earthen material capable of sustaining native plant growth will be provided to minimize wind and water erosion of each pond's final cover system. The final protective layer will cover the entire low permeability layer in each pond's final cover system and will be installed as soon as possible after placement of the low permeability layer. An appropriate seed mixture will be selected to minimize root penetration into the infiltration-control layer. Finally, a final protective layer thicker than the 3-foot minimum is not warranted because freezing temperatures and freeze-thaw conditions will not affect the hydraulic performance of the HDPE geomembrane liner being utilized as the low permeability layer in each pond's final cover system (Ref. 5).

4.0 ESTIMATED MAXIMUM INVENTORY OF CCR

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(1)(D)

Federal CCR Rule Reference: 40 CFR 257.102(b)(1)(iv)

Detailed records of the maximum inventories of CCR ever stored in South Ash Ponds 2 and 3 are not available. For the purposes of this preliminary written closure plan, the maximum CCR inventories for South Ash Ponds 2 and 3 are conservatively based on their estimated maximum capacities, which are 21,300 and 24,400 cubic yards, respectively.

5.0 ESTIMATED COVER SURFACE AREA

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(1)(E)

Federal CCR Rule Reference: 40 CFR 257.102(b)(1)(v)

The estimated final cover surface areas for South Ash Ponds 2 and 3 are 2.2 and 2.4 acres, respectively. It is estimated that these areas represent the largest surface areas that will ever require final covers at any point over the ponds' active lives.

6.0 CLOSURE SCHEDULE

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(1)(F)

Federal CCR Rule Reference: 40 CFR 257.102(b)(1)(vi)

Closure activities are anticipated to be performed concurrently for both South Ash Ponds 2 and 3 and are estimated to be completed in 2025. Table 3 lists the major milestones necessary for closing both ponds and the expected duration for completing each milestone.

Table 3 – Planning Level Schedule for Closing South Ash Ponds 2 & 3

Activity	Estimated Duration
Prepare Closure Construction Design Documents	7 Months
Obtain Closure Construction Permit from Illinois EPA	11 Months
Hire Contractor to Complete Closure Activities in Accordance with Illinois EPA Permit	4 Months
Draw Down Water & Dewater Impounded Ash	4 Months
Grade Dewatered Ash	1 Month
Install Final Cover System	2 Months
Submit Closure Report and Certification to Illinois EPA	2 Weeks
Obtain Approval of Closure Report and Certification from Illinois EPA	3 Months
Complete and Certify Closures of South Ash Ponds 2 and 3	--

7.0 AMENDMENTS TO CLOSURE PLAN

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(3)

Federal CCR Rule Reference: 40 CFR 257.102(b)(3)

This preliminary written closure plan will be amended in accordance with 35 Ill. Adm. Code 845.720(a)(3) and 40 CFR 257.102(b)(3) if a change in the operation of either South Ash Pond 2 or South Ash Pond 3 would substantially affect this closure plan or if an unanticipated event necessitates a revision to this closure plan. Any and all amendments to this closure plan will be certified by a qualified professional engineer registered in the State of Illinois in accordance with 35 Ill. Adm. Code 845.720(a)(4) and 40 CFR 257.102(b)(4).

8.0 COMPLETION OF CLOSURE ACTIVITIES

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.760

Federal CCR Rule Reference: 40 CFR 257.102(f)

Upon completion of all closure activities required by 35 Ill. Adm. Code Part 845 and 40 CFR 257.102(d) and approved by the Illinois EPA in a construction permit, a closure report and a closure certification for South Ash Ponds 2 and 3 will be submitted to the Illinois EPA in accordance with 35 Ill. Adm. Code 845.760(e). The closure report will include (1) the engineering and hydrogeology reports containing any monitoring well completion reports, boring logs, all construction quality assurance (CQA) reports, certifications, designations of CQA officers-in-absentia required by 35 Ill. Adm. Code 845.290; (2) photographs with time, date, and location information relied upon for documentation of construction activities; (3) a written summary of the closure requirements and completed activities as stated in the closure plan in effect and 35 Ill. Adm. Code Part 845; and (4) any other information relied upon by the qualified professional engineer for certification. Pursuant to 35 Ill. Adm. Code 845.760(e)(2) and 40 CFR 257.102(f)(3), the certification will be prepared by an independent, qualified professional engineer licensed in the State of Illinois and will verify that South Ash Ponds 2 and 3 have been closed in accordance with the closure plan in effect at the time of the closure work, the requirements of 35 Ill. Adm. Code Part 845, and the requirements of 40 CFR 257.102. Finally, within 30 days of the Illinois EPA approving the closure report and closure certification, a notification of completion of closure will be prepared in accordance with 35 Ill. Adm. Code 845.760(f) .

9.0 CERTIFICATION

Illinois CCR Rule Reference: 35 Ill. Adm. Code 845.720(a)(4)

Federal CCR Rule Reference: 40 CFR 257.102(b)(4)

I certify that:

- This preliminary written closure plan for South Ash Ponds 2 and 3 was prepared by me or under my direct supervision.
- The work was conducted in accordance with the requirements of 35 Ill. Adm. Code Part 845 and with the requirements of 40 CFR 257.102.
- I am a registered professional engineer under the laws of the State of Illinois.

Certified By: Thomas J. Dehlin

Date: October 29, 2021

Seal:



Th. J. Dehlin
10/29/2021
Exp. 11/30/2021

10.0 REFERENCES

1. Illinois Pollution Control Board. "Standards for Disposal of Coal Combustion Residuals in CCR Surface Impoundments." 35 Ill. Adm. Code 845. Accessed October 19, 2021.
2. U.S. Environmental Protection Agency. "Standards for Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments." 40 CFR Part 257 Subpart D. <https://www.ecfr.gov/current/title-40/chapter-I/subchapter-I/part-257/subpart-D>. Accessed October 19, 2021.
3. Giroud, J.P. and Bonaparte, R. "Leakage through liners Constructed with Geomembranes—Part I. Geomembrane Liners." *Geotextiles and Geomembranes*. Vol. 8. pp. 27–67. 1989.
4. National Oceanic and Atmospheric Administration. "Point Precipitation Frequency (PF) Estimates." NOAA Atlas 14, Volume 2, Version 3. https://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html. Accessed October 19, 2021.
5. Hsuan, Y. *et al.* "Cold Temperatures and Free[ze]-Thaw Cycling Behavior of Geomembranes and Their Seams." GSI White Paper #28. Geosynthetic Institute. June 17, 2013.